



**KENT COUNTY DEPARTMENT OF PUBLIC WORKS
COUNTY ENGINEER**

709 Morgnec Road
Chestertown, MD 21620
410-778-2600
Fax 410-778-7424

Michael S. Moulds, P.E.
Director
mmoulds@kentgov.org

James M. Wright, Jr., P.E.
County Engineer
jwright@kentgov.org

August 28, 2020

RFP #PL 21-01
For The
Pier & Mooring Pile Replacement
At
Quaker Neck Public Landing

Addendum No. 1

The following clarification to questions discussed at the pre-bid meeting are hereby made a part of the RFP specifications. **Bidders must acknowledge receipt of this addendum in their bids.**

1. Pile Size & Spacing. All piles are to be 35 ft. long with 10'- 0" c-c spacing along the pier.
2. Piles located under the "ell" portion of the pier shall not require plastic caps, only sealant.
3. A question was received asking if the pier framing and decking was subject to the DNR waterfowl staging area time of year restrictions. The answer from Roland Limpert at DNR was, yes, it is subject to that restriction. It is considered "in water" work.

