



1. INSTALL PLUMB - PROVIDE TEMPORARY BRACING TO MAINTAIN POSITIONING DURING CONCRETE PLACEMENT.
2. THE CONCRETE ANTI FLOATATION COLLAR SHALL BE AS PER MANUFACTURER'S RECOMMENDATION.
3. ONCE THE CONCRETE ANTI FLOATATION COLLAR HAS BEEN POURED AROUND THE PUMP UNIT, IT SHALL BE LIFTED USING THE BENT REBAR LIFTING EYES ONLY. NO OTHER METHOD IS ACCEPTABLE

4. CONTRACTOR TO USE STAINLESS STEEL ADAPTER TO 1-1/4 FEMALE PIPE THREAD AT DISCHARGE, NIPPLE AND PIPE TO ELBOW, AND RUN VERTICALLY UP OUTSIDE OF PUMP CHAMBER TO 48" DEPTH FOR DISCHARGE.
5. CONTRACTOR TO INSTALL STAINLESS STEEL GATE VALVE WITH A VALVE BOX ON 48-INCH DEEP DISCHARGE LINE.

SEWAGE GRINDER PUMP UNIT INSTALLATION

DATE: 01/10/2018